

MYSORE DISTRICT.

Notice dated 26th February 1913.

The "Dodda Jatra" of Sri Srikantesvaraswami at Nanjangud will take place on the 20th March 1913, and, as usual, there may be a large concourse of people. As cholera has broken out at Nanjangud in a virulent form, the pilgrims are hereby warned that they run the risk of catching the infection, if they visit the place during the jatra occasion.

K. CHANDY,
Deputy Commissioner.

OFFICE OF CHIEF ELECTRICAL ENGINEER, BANGALORE.

Abstract Notification.

It is hereby notified that sealed tenders will be received at the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 24th March 1913, for collecting about 15,000 cubic yards of broken granite for Bangalore Electric Tramways.

For further particulars, *vide* page 346 of Part II of the *Mysore Gazette*, dated 6th March 1913.

C. F. BEAMES,
Chief Electrical Engineer to the Government of Mysore.

BANGALORE DIVISION.

Dated (Camp) Fern Hill, 10th March 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 31st March 1913, for restoring the Handrahalli Tank, Registered No. 57, Devanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred (300) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Handrahalli Tank, Registered No. 57, Devanhalli Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Restoring Handrahalli Tank, Devanhalli Taluk.

Items of work.	Unit of work.	Quantity.
BUND.		
Clearing bushes	Lump sum	Rs.
Earthwork	C. yd.	5,555
Conveying 1 furlong up to C. S. 7 from waste weir draft cutting.	Do	1,440
Old stone work	Do	300
New stone work (burnt stone)	Do	1,467
Gravel backing with lead	Do	536
Turfing	Sq. yd.	5,115
New grade stone	Each	27
Index stones	Do	27
Gauge stone (new stone pattern)	Do	1
B. M. Stones	Do	2
Registered number stone	Do	1
Date stone	Do	1
NEW SLUICE.		
Earthwork	C. yd.	270
Dismantling and removing the old tunnel above and floor level.	Lump sum	Rs.
Burnt brick in chunam	C. ft.	787
Burnt stone slabs	S. ft.	378
Cutting orifices	No.	4
Rough chunam, surki plastering	Sq.	6.16
Nice plastering, chunam	Do	3.00
Plug with iron rod, chain, lock and key, etc.	Each	1
WASTE WEIR.		
Earthwork, cutting draft and approach	C. yd.	1,940
Earthwork, excavation for foundation	Do	139
Burnt brick in surki mortar	C. ft.	1,187
Burnt stone slabs	S. ft.	763
Plastering with surki mortar	Sq.	5.59
Rough stone work new (burnt stones)	C. yd.	187
Stone pins to the joints of coping slabs	Each	21

Dated 13th March 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 31st March 1913, inclusive, for extending the Government Press building at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for extending the Government Press building at Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Extending the Government Press building at Bangalore.

No.	Items of work	Per	Rate	Quantity	Cost	Remarks
			Rs. a. p.		Rs. a. p.	
1	Earthwork, excavation and filling basement ...	C. yd.		724		
2	Concrete	C. ft.		5,407		
3	Stone in chunam, foundation	"		9,412		
4	Do basement	"		3,761		
5	Burnt brick in mortar	"		16,668		
6	Stone slabs, 6" thick	S. ft.		938		
7	Brick in mortar, archwork	C. ft.		1,448		
8	Teakwood, strong pannelled doors with brass locks, hinges, etc., complete.	S. ft.		400		
9	Teakwood windows, glazed and veneitioned shutters with iron bars, etc., complete.	"		336		
10	Teakwood windows pannelled and glazed shutters with iron bars, etc., complete.	"		160		
11	Teakwood semi-circular fanlights over doors and windows with glazed swing shutters.	"		236		
12	Chunam plastering	Sq.		231'40		
13	Pointing basement with mortar	"		17'36		
14	Rolled steel girders and joists with painting, etc., complete.	Cwt.		314'71		
15	Teakwood work with wood oiling, etc., complete.	C. ft.		81'0		
16	Terrace, complete	Sq.		8'27		
17	Roofing with jack arches	"		43'82		
18	Flooring with clay tiles over 3" concrete and cement pointing.	"		32'06		
19	Flooring with Cuddappah slabs over 3" concrete and cement pointing.	"		3'16		
20	Cornice work, thick	R. ft.		404		
21	Do thin or light	"		274		
22	Whitewashing	Sq.		174'0		
23	Colorwashing	"		57'89		
24	String course	R. ft.		104		
25	Cast iron down ware pipes, etc.	L. S.		...		
26	Drainage around the building	"		...		
27	Clearing site... ..	"		...		
28	Painting doors, etc.	Sq.		27'12		
29	Iron gate	L. S.		...		
30	Brick in mortar coping with glass pieces	R. ft.		160		
31	Do parapet in front	"		166		
32	Do do in rear	"		230		

J. E. A. D'CRUZ,
Executive Engineer.

TUMKUR DIVISION.

Dated 3rd—4th March 1913.

The attention of the public is invited to Notification dated 4th March 1913, published in the *Mysore Gazette* calling for tenders for improving the Nandihalli tank, Regd. No. 163 and excavating a feeder channel therefrom to Maidala Amanikere Regd. No. 155, Tumkur Taluk.

C. VIJAYARANGAM NAIDU,
Officiating Executive Engineer.